



Weller Systems, LLC

1590 Garnet School Rd
Dahlonega, GA 30533
(706) 867-0171

Contact: Eric Weller

Phone:

Fax:

Email: eric.weller@wellersystems.com

Date: [6/21/2007](#)

Estimate ID: 85

Estimate Code: Concrete Slab Modifications

Project: Concrete Slab Modifications

Component Description	Quantity Needed	Order UOM	Material Cost
-----------------------	-----------------	-----------	---------------

Category: CONCRETE

#5 Rebar - 5/8"	757.000	LF	
3000 PSI With Fiber	37.400	CUBYD	
42"x30" #3 Stirrup	44.000	EA	
66"x30" #3 Stirrup	27.000	EA	
Foundation Chairs (2 Bar)	92.000	EA	

Category: LABOR

Concrete Mason (Helper)	14.000	HR	
Concrete Mason (Skilled)	14.000	HR	
Mason Labor (Helper)	23.000	HR	
Mason Labor (Skilled)	14.000	HR	

Category: RENTAL

Bobcat 763 (Daily Rate)	0.268	DAY	
Concrete Pump Per Hr.	5.000	HR	
Cut off Saw Brick / Block Gas	0.301	DAY	
Dumpster 20 Yd	1.000	EA	